

1 Q. Restoration of Holyrood Unit 1: Please state whether there are any continuing  
2 issues with the Holyrood Unit 1 turbine-generator that may have resulted from the  
3 damages of January 2013 and whether the vibration issue that persisted through  
4 2013 and into 2014 has been eliminated.

5

6

7 A. Following the repairs to the unit in 2013, balancing runs were completed on Unit 1  
8 to bring it within the requirements of unrestricted operation for the winter of  
9 2013/2014. Following the 2014 maintenance outage on Unit 1, further balancing  
10 runs were completed, which enabled the unit to be able to go through its start-up  
11 sequence more quickly than the experience in 2013/2014, while continuing to meet  
12 ISO-7919-2 guidelines for unrestricted, long-term operation. With the maintenance  
13 and balancing work carried out, Hydro is confident that Unit 1 can be run in  
14 accordance with the ISO guidelines.