

1 Q. **Tab D – Projects Over \$200,000 and Less Than \$500,000: p. D-95 – Replace**
2 **Vibration Monitoring System Unit 7, Bay d’Espoir**

3 Will this project, and Hydro’s plans for the future, address all the recommendations
4 set out at pages D-154 and D-155?

5

6

7 A. This project, and Hydro’s plans for the future, will address all recommendations set
8 out at pages D-154 and D-155 with the exception of recommendation #6.

9

10 With respect to recommendation #6, Hydro has considered this recommendation.
11 An approved work procedure (AWP) would gain little time as the majority of time
12 required for a balancing run is the time to de-water and water up the penstock,
13 work components which remain the same whether using an approved work
14 procedure or not.