## Page 1 of 2

Q. The costs estimated by Stantec for the ESP and FGD installations in their report are 1 2 totaled at \$450 million. The price carried in document "Exhibit 5 Summary Capital 3 Cost Estimate" is \$582 million. In discussions with Nalcor on August 17, 2011, Nalcor indicated that there was a capital budget input sheet that was submitted to 5 the System Planning Department which developed these costs. Please describe the 6 progression of these costs from \$450 million to \$582 million. 7 8 9 A. The \$450 million total cost in the Stantec report, Table 8.1 (see Exhibit 5L-i: 10 Precipitator and Scrubber Installation Study – Holyrood Thermal Generating Station - Final Report, November 21, 2008) is in third quarter 2008 dollars and does not 11 include overhead cost, AFUDC or other owner's costs. The \$582 million cost carried 12 13 in document "Exhibit 5 Summary Capital Cost Estimate" is in-service in 2015 and 14 includes corporate overheads, escalation and AFUDC. 15 16 Please see the following page for a copy of the Capital Budget Proposal sheets and 17 the detailed calculation showing the progression from \$450 million to \$582 million.

Prepared by:			CAPITAL BUDGET PROPOSAL											
			Capital Cost Estimate & Cash How Requirements					Holyrood Precipitator/Scrubber Installation						
				2010 Fiscal Year Prepared:					In-Service: Other					
	AFUDC =	7.5%	Annual	0.61%	Monthly	1.83%	Quarterly	Effective	Corp O/H @	0.81%	Iffective Con	tingency Ø	11.7%	
Escalation	2009 -	1.4%	2010-	0.5%	2011 -	1.7%	2012 -	2.3%	2013 -	3.0%		Est. Base:	2009, January	
	2014-	3.1%	2015 -	20%	2016 -	1.5%	2017 -	2.7%	2018 -	27%	2019 -	2.5%		
	2020 -	2.5%	2021 -	25%	2022 =	2.5%	2023 =	2.5%	2024 -	2.5%	2025 =	2.5%		
-	Cost Type	1110	1120	1130	1135	1140	1145	1150	1160	1175		1165	Total	1170 Cost
Period	**********	Labour	O/T	Material	Consultant	Rippip Rombil	Travel	Contract Wo	& Corp. O/H	Contingency	Piscin	AFUDC	Project	Recoveries
TOTAL	ROJECT	5,151.3	0.0	0.0	31,833.6	0.0	704.9	360,433.	0 4,577.9	59,718.4	30,393.6	76,442.5	569,254.7	0.0

All figures in thousands of dollars.

Labour 5,151.3 Consultant 31,833.6 Travel 704.9 Contract Work 360,433.0 Contingency 59,718.4 Total Directs 457,841.2 2009\$

Total Directs 457,841.2 2009\$ Corp. O'H 4,577.9 Escalation 30,393.6 APUDC 76,442.5 Total Project 569,255.2 2014\$

See Cover - Completion Date 2.2% 12,523.6 Escalated from 2014 In-Service

to 2015 In-service.

The Total from Table 8.1 Stantec Report ( Exhibit  $SL_i$ ) = \$450,000 Prom Appendix A, this is in 3rd quarter 2008 dollars.

581,778.8 2015\$

As stated in Section 8.1 of the Stantec Report, the estimate does not include overhead costs, AFUDC or other owner's cost.

The original Capital Budget Proposal was prepared in 2009 for an in-service date of 2014. For the 2010 generation expansion runs, the Total Project Cost was escalated to 2015\$, to coincide with the proposed 2015 in-service date.